AD A 0 9 0 7 5 0



USAARL REPORT NO. 80-7

# LEVELI

SPH-4 HELMET DAMAGE AND HEAD INJURY CORRELATION

DTIC ELECTED OCT 24 1980

By Bruce A. Slobodnik

HUMAN TOLERANCE AND SURVIVABILITY DIVISION

Biomedical Tolerance

September 1980

U.S. ARMY AEROMEDICAL RESEARCH LABORATORY FORT RUCKER, ALABAMA 36362

USALIS.

### NOTICE

## Qualified Requesters

Qualified requesters may obtain copies from the Defense Documentation Center (DDC), Cameron Station, Alexandria, Virginia. Orders will be expedited if placed through the librarian or other person designated to request documents from DDC.

# Change of Address

Organizations receiving reports from the US Army Aeromedical Research Laboratory on automatic mailing lists should confirm correct address when corresponding about laboratory reports.

## Disposition

Destroy this report when it is no longer needed. Do not return it to the originator.

# Disclaimer

The views, opinions, and/or findings contained in this report are those of the authors and should not be construed as an official Department of the Army position, policy, or decision, unless so designated by other official documentation. Citation of trade names in this report does not constitute an official Department of the Army endorsement or approval of the use of such commercial items.

Reviewed:

J<del>e</del>rod L. Goldstein, MAJ, MSC

Acting Director, Human Tolerance and Survivability Division

Survivability bivision

Chairman, Scientific Review

Committee

Released for Publication:

STANLEY C. KMAPP Colonel, MC

Commanding

SECURITY CLASSIFICATION OF THIS PAGE (When Date Entered)

	REPORT DOCUMENTATI	ON PAGE	READ INSTRUCTIONS BEFORE COMPLETING FORM
J	REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
1	USAARL Report No -80-7	10-1040 750	9
1	TITLE (and Subtitle)	The first state of the state of	5. TYPE OF REPORT & PERIOD COVERED
1	SPH-4 Helmet Damage and Head I	njury Correlation .	/Final to 2. Lyg min
1		·	6. PERFORMING ORG. REPORT NUMBER
ſ	7. AUTHOR(a)		8. CONTRACT OR GRANT NUMBER(*)
	Bruce A./Slobodnik		
ſ	Performing organization name and additional Human Tolerance and Survivabil		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
Ĭ	US Army Aeromedical Research L		6.27.73.A,
	Fort Rucker, Alabama 36362	/	/ 3E162773A819 / / Ø0 / 015
-	US Army Medical Research and D	ovolopment Compard	2. REPORT DATE
ı	Fort Detrick	everophient command	September 1980
١	Frederick, Maryland 21701		23 /- 1_2.7 ]
	14. MONITORING AGENCY ILAME & ADDRESS(IT di	flerent from Controlling Office)	15. SECURITY CLASS. (of title report)
ı			Unclassified
l			15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
l	16. DISTRIBUTION STATFMENT (of this Report)	<del></del>	
ı	Approved for public release, o	distribution unlimit	ed.
1	, and the parties of the control of	arsor regordic antrimity	. 7
ı			
l			
Į	17. DISTRIBUTION STATEMENT (of the abatract on	tered in Block 20, if different fro	m Report)
ı			
ı			
١			
1	18. SUPPLEMENTARY NOTES	thin wassut his biss	- multitation ( ) A + ( )
	Some of the data contained in Space, and Environmental Medic Proceedings No. CP-253	ine, Feb 78, and (b)	NATO-AGARD Conference
ł	19. KEY WORDS (Continue on reverse side if necess	ary and identify by block number)	
I		concussion	
1	crash damage simulation	unconsciousness	
ı	head impact tolerance		
١	helmet impact tests		;
	20. ABSTRACT (Craftmin en reverse elde il nacessa	ey and identify by block number)	
	See reverse.		
١			
ı			
1			

DD 1 JAN 73 1473

EDITION OF ! NOV 68 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Date Entered)

40,200

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## 20. ABSTRACT:

Human tolerance to head impact was assessed by correlating the force levels required to duplicate damage seen in 12 SPH-4 aviator helmets retrieved from US Army helicopter crashes with resulting head injury. Head injury occurred at peak acceleration levels far below 400 G, which is the value currently used by the US Army as the pass-fail criterion in evaluating the impact attenuation performance of prospective aircrew helmets. Concussive head injuries occurred below Severity Index values of 1500 and below Head Injury Criterion values of 1000. These are considered concussive threshold values by the National Operating Committee on Standards for Athletic Equipment and by the Department of Transportation, respectively.

Access	ion For	
177.5		X
r no r		
$t_{I}$ which	unced	L.I
រូប្រាប់ដ	ication	1
11		
Distr	ibution.	/
Avai	labilit	A Cogea
	Avail a	
Dist	Spec	ial
1	1 1	

## **ACKNOWLEDGEMENTS**

The author wishes to thank SP5 Thomas Simson and Mr. Ted Hundley for their invaluable assistance in instrumentation, data collection and analysis.

This report is a compilation of two reports previously published in *Aviation*, *Space*, and *Environmental Medicine*, Volume 50, and AGARD Conference Proceedings No. 253.

This work was accomplished by LT Slobodnik while assigned to USAARL as Naval Liaison Officer during the period April 1975 through June 1979. LT Slobodnik is presently assigned to Systems Engineering Test Directorate, Air Crew Systems Branch, Naval Air Test Center, Patuxent River, MD.

# TABLE OF CONTENTS

																					Page No.
List of Illustrations	٠							•				•							•		4
Table	•		•	•		•	•	•	•			•	•		•			•	•	•	4
Introduction		•	•			•	•		•		•				•					•	5
Materials and Methods		•	•			•				•	•	•									5
Results		•	•			•	•		•	•	•	•			•	•		•	•	•	12
Discussion			•	•	•		•			•		•			•	•					12
Conclusions	•	٠	•	•	•	•		•	•				•	•	•			•		•	17
References																	_				18

# LIST OF ILLUSTRATIONS

FIGURE		Page No.
1	Impact Sites	6
2	Helmet Drop Tower	7
3	Suspension Strap Anchor Clip Bending	8
4	Helmet Liner Damage	9
5	Fiberglass Helmet Shell Fracture	10
6	Graphs of Cases Synchronized in Time	11
7	Peak Acceleration Values	13
8	Severity Index Values	13
9	Head Injury Criterion Values	15
10	Peak Transmitted Force Values	16
	TABLE	
	Summary of Impact Damage Duplication Data For 14 Helmets Retrieved From US Army Helicopter Accidents	14

### INTRODUCTION

The ANSI Z90.1-1971 (1971) method, called out in Military Specification MIL-H-43925 (DA 1975) and currently used by the US Army for evaluating the impact attenuation performance of prospective aircrew helmets, relies primarily on peak G as a pass-fail criterion. A candidate helmet is attached to an instrumented metal headform and dropped from a height yielding 95 joules of input energy onto a 4.8-cm radius steel hemisphere. Helmets which prevent the peak acceleration experienced by the headform in such impacts from exceeding 400 G meet the Army standard for impact performance and qualify for use by Army aircrewmen. However, based on the incidence of head injury in survivable Army aircraft accidents, it can be questioned whether or not the current Army standard adequately reflects hum in tolerance limits to head impact. This paper will attempt to answer that question.

To date, efforts to define human tolerance to head impact have been confined, necessarily, to studies involving animals or human cadavers. However, in 1972 the Army's establishment of the Life Support Equipment Retrieval Program provided a unique opportunity to research directly human tolerance limits to head impact. Since 1972, helmets involved in Army aircraft accidents worldwide have been retrieved for laboratory analysis. If it is assumed that the damage seen in a retrieved helmet accurately reflects the force experienced by the wearer's head in the crash situation, then those force levels can be identified by duplicating that degree of damage on a similar helmet under controlled conditions. By comparing force levels to resulting head injury, human tolerance limits to head impact can be defined.

## MATERIALS AND METHODS

A total of 12 SPH-4 helmets was selected for impact damage simulation from those flight helmets analyzed in the retrieval program to date. Two of the helmets had received two impacts each; however, neither of the helmet wearers received head injuries from the impacts, so each impact was considered independent of the other for a total of 14 impact cases.

These 12 simulation helmets were selected because the impact was not a glancing blow; thus, all head injury is assumed to have resulted primarily from translational acceleration. The centers of the impact locations on both the helmet and the head for the 14 cases selected for impact damage duplication is summarized in Figure 1. The impact locations shown on the helmet shell are precise; those on the head are approximate since some relative movement is possible between the helmet and head during the impact.



FIGURE 1. Of the 14 cases studied, 6 were frontal impacts, 4 were crown, 2 were side, and 2 were located at the back of the head. The center of each impact shown on the helmet is precise; those of the head are only approximate since some movement between helmet and head is possible during impact.

Spare helmet components were assembled to produce several duplicates for each of the 14 cases. Each duplicate helmet was prepared so that its shell thickness, liner thickness, and adjustment of suspension straps matched that of the retrieved helmet as closely as possible. To reproduce the damage of a given retrieved helmet, duplicates for that helmet were attached to a modified version of the humanoid headform specified by the National Operating Committee on Standards for Athletic Equipment (NOCSAE) for evaluating football helmets (Hodgson 1975). As shown in Figure 2, the head-neck connection of this headform was modified to increase its adjustability and permit mounting on the standard carriage

assembly specified by the ANSI 790.1-1971 method. A tri-axial accelerometer (Endevco Model 2267C-750)\* was positioned at the head form's center of mass. Its signal was amplified by a signal conditioner (Endevco Series 4470)\* and fed to a three-channel vector analyzer. The vector resultant




FIGURE 2. Retrieved helpet damage was duplicated by attaching a test helmet to this instrumented humanoid head form and impacting it onto a surface of appropriate shape. Peak transmitted force was measured using the resultant of three force transducers located beneath the impact surface. Drop height was varied until the best damage duplication was achieved.

<sup>\*</sup> Enveco Model 2267X-750, Becton, Dickinson & Co., Rancho Viejo Rd San Juan Capistrano, CA 92675.

of the three accelerometer signals was then transmitted to the hybrid computer, which computed the values of peak G, Severity Index (SI) as described by Gadd (1966), and Head Injury Criterion (HIC) as defined by Chou and Nyquist (1974). Total weight of the head form and carriage was 5 kg.

The helmeted head form was then dropped onto an impacting surface that had been selected to reproduce the type of damage seen on the retrieved helmet. Some helmets required a concave impact surface to duplicate the area of compression seen in the foam helmet liner. These concave impact surfaces were prepared by taking an impression of the helmet shell at the impact site using dental cement. These cement impressions were then used as impact surfaces. Three piezoelectric force transducers (Kistler type 9021)\* were positioned beneath the impact surface as shown in Figure 2. The drop height was varied until the damage produced in the duplicate helmet matched that of the retrieved helmet.

Damage was assumed to have been duplicated when a) the amount of bending in the six suspension strap anchor clips was duplicated, as shown in Figure 3; b) the area and maximum deflection of the foam helmet liner was duplicated, as shown in Figure 4; and c) the degree of fracture




FIGURE 3. The amount of bending in the six suspension strap anchor clips was duplicated for each of the 14 cases.

<sup>\*</sup> KIAG Swiss, Kistler Instrumente AG, CH 8408, Winterthur, Switzerland.




FIGURE 4. Helmet liner damage was duplicated by matching the area and maximum compression produced in the test helmet liner with that of the retrieved helmet liner. Maximum compression was duplicated to within a few thousandths of an inch.

in the fiberglass helmet shell, as shown in Figure 5, matched that of the retrieved helmet. Acceleration vs. time and force vs. time traces were recorded for each impact and are shown in Figure 6. A description of head injuries associated with any of the 14 cases was obtained by reviewing the official accident report supplied by the US Army Safety Center. All head injuries were assigned a severity value using the Abbreviated Injury Scale (AIS) (1976).





FIGURE 5. The degree of fracture in the fiberglass helmet shell was duplicated for those cases in which shell fracture occurred.



CASE # 4 HIC 4437 SI 4847 Drop HI 128 cm helmet weight causes some separation between helmet and headform permitting

the helmet to rebound initially inde-

pendently of the headform.

### **RESULTS**

A description of head injuries, of conditions required to duplicate helmet impact damage, and of the data recorded for each of the 14 cases is shown in Table 1. Only three of the 14 cases required an impact surface more severe than that of a flat surface to duplicate the helmet damage. In all eight cases involving head injury, the foam helmet liner was not compressed to the maximum extent possible. Only in case No. 5 did head injury result from the impact surface penetrating the helmet shell. All three cases in which fracture occurred involved forcing the head down against the spinal column resulting in either basilar skull fracture or fracture of the first cervical vertebra.

The peak acceleration judged to have been experienced in the 14 cases comprising this study, based on the best damage duplication, is shown in Figure 7. Head injury occurred well below the 400-G criterion currently used by the US Army in evaluating the impact performance of prospective aircrew helmets.

SI and HIC values were calculated for each of the 14 cases and are shown in Figure 8 and 9 respectively. Concussive head injuries occurred at SI values below 1500, which is the value currently used as the concussive threshold by NOCSAE in evaluating the impact performance of football helmets. Concussive head injuries also occurred at HIC values below 1000, which is the value currently adopted by the Department of Transportation (DOT) in Federal Motor Vehicle Safety Standard No. 208 (1972) for occupant crash protection tests as the limit of human tolerance for impact to the unprotected head.

### DISCUSSION

The low incidence of penetrating types of head injuries among Army helicopter crash victims appears to be due primarily to a) an absence of sharp, rigid cockpit surfaces, and b) the effectiveness of the SPH-4 aviator helmet as a load-spreading device.

On the other hand, the energy-absorbing capability of the helmet appears inadequate based upon the high incidence of concussive types of head injuries observed. This deficiency can have disastrous effects, as seen in cases 4 and 6 where basilar skull fracture occurred as a result of the helmet transmitting, rather than absorbing, the impact force. Recent in-house studies (unpublished) have shown that the energy-absorbing ability of the helmet can be more than doubled by simply increasing the thickness and decreasing the density of the foam helmet liner.




FIGURE 7. Peak acceleration values for the impact best duplicating helmet damage for each of the 14 cases. Solid bars represent cases in which head injury resulted from the impact. Head injury occurred at peak acceleration level well below 400 G.




FIGURE 8. Severity Index values for the impact best duplicating helmet damage for each of the 14 cases. Solid bars represent cases in which head injury resulted from the impact. Concussion occurred below the SI value of 1500 used by NOCSAE as the concussive threshold. See Table 1 for a description of head injuries.

TABLE 1

SUMMARY OF IMPACT DAMAGE DUPLICATION DATA FOR 14 HELMETS RETRIEVED FROM US ARMY HELICOPTER ACCIDENTS

AIS	0	0 0 0	2	Q	0	0 0	ı	2	2	r.	rU
Head Injury Description	none dazed several	minutes none basilar skull	scious 30 hours subdural hema-	none	none	none	2 min, semi- conscious 6 hours.	fracture of C <sub>1</sub> deep scalp laceration, dazed several	minutes unconscious	several minutes unconscious 100 heurs	basilar skull fracture with subarachnoid hemorrhage fatal
Impact Energy (3)	2 <b>4</b> 29	34 48 97	121	10	53	29 145	2	97	77	107	208
Total Liner Area Com- pressed (cm <sup>2</sup> )	none 17.0	20.6 14.6 21.3	45.6	none	none	none		14.7	26.8	25.0	13.2
Maximum Liner Com- pression After Impact	none 38	13 39 43	52	none	none	none 24	5	78	63	51	14
Helmet Liner Thickness Before Impact (cm)	0.983	1.054 1.021 1.029	0.983		ı	1 110	) 4	1.029	0.909	1.080	0.991
Peak Force (N)	3140 3200	4820 6180 17200	14860	1000	3520	4200		0089	11680	10060	13360
HIC	63	214 228 2252	2872	17	33	109		553	1379	901	4432
SI	70 123	239 285 2458	3477			125		629	1571	1019	4849 4432
Pulse Dura- tion (ms)	7.2	7.0 13.0 4.5	6.5	16.8	17.4	10.6	, ,	11.3	8.3	10.9	8.1
Average Accel- eration (G)	88 88	55 40 139	136	14	18	9 4 5	Ĉ.	54	31	29	133
Peak Drop Accel- Ht. eration (m) (G)	60 73	96 117 322	355			77		141	263	184	415
: 9-:1	0.38	0.53 0.76 1.52	1.91	0.15	9.46	0.46	6.67	1.52	1.22	1.68	3.28
Shape of Drc Impact Ht Surface (m)	flat 0.38 concave 0.46	flat flat flat	concave	flat	flat	tlat *0d	1.27 cm radius	bolt head 1.27 cm	diameter flat	hemî- sphere 4.83 cm	concave
Impact Loca- tion	front front	front front front	front	Crown	Crown	Crown		back	back	s i de	side
Case No.	13.2	10 12 6	14	က	σ	Ξ°	)	ĸ	7	-	4





FIGURE 9. Head injury criterion values for the impact best duplicating helmet damage for each of the 14 cases. Solid Bars represent cases in which head injury results from the impact. Concussion occurred below the HIC value of 1000 used by DOT. See Table 1 for a description of head injuries.

The pass-fail criterion currently used by the Army to evaluate the impact performance of prospective aircrew helmets does not appear related to human tolerance limits to head impact. In seven of the eight cases in which head injury did occur, a helmet permitting the peak acceleration experienced by these individual heads would have passed the current Army impact performance standard set at 400 G as shown in Figure 7. It would appear that the pass-fail criterion currently used by the Army selects helmets which, for the most part, prevent death in crash situations but certainly do not prevent concussive head injury. Considering the potentially hostile post-crash environment--such as fire, drowning, and capture--the injury level permitted by the current pass-fail criterion is unacceptable. To be effective in selecting aircrew helmets to prevent concussive head injuries in survivable helicopter crashes, the pass-fail criterion should be set at no higher than 150 G, as can be seen in Figure 7. Even though Snively and Chichester (1961) reported that man can withstand helmeted head impacts exceeding 450 G, he was referring to surviving the initial impact only, not a helicopter post-crash environment. Based on case No. 4, where a fatal head injury resulted from a peak acceleration of 415 G, it can be questioned whether or not even an initial impact of 450 G could be survived with any degree of certainty.

Swearingen (1971) duplicated the impact conditions involving the crash of a military helicopter. He reported that the pilot involved received a frontal head impact and experienced a peak acceleration of 435 G without sustaining any head injury. Even though differences exist between individuals in their tolerance to head impact, it seems highly unlikely that very many individuals exist who could withstand head acceleration of this magnitude without experiencing at least concussion. As shown in Figure 7, the peak acceleration associated with all eight cases involving head injury in this study fell below 435 G. In particular, cases 6 and 14 were frontal impacts in which very severe head injuries resulted (AIS value 5) from peak accelerations of 322 G and 355 G, respectively.

The values of peak transmitted force were recorded for each of the 14 cases in an attempt to validate the value of 5000 lb (22.3 kN) currently specified in British Standard 2495 (1960) as the limit of survivability for helmeted head impacts. As shown in Figure 10, the one case of fatal head injury occurred at a peak transmitted force of 2982 lb (13.3 kN). In addition, severe head injury occurred (AIS value 5)

FIGURE 10. Peak transmitted force values for the impact best duplicating helmet damage for each of the 14 cases. Solid bars represent cases in which head injury resulted from the impact. Cases 6, 14, 1, and 4 had an AIS value of 5 with case 4 being fatal.



16

in cases 6, 14, and 1 at peak transmitted force values of 3839 lb (17.1 kN), 3317 lb (14.8 kN), and 2246 lb (10 kN) respectively. It would appear that a peak transmitted force value of 5000 lb exceeds the limit of survivability.

To what extent the SI value of 1500 or the HIC value of 1000 should be lowered to increase its effectiveness as a predictor of concussion is difficult to establish on the basis of only 14 cases. Continuing this research effort on helmets as they become available should help to define these concussive threshold values.

## CONCLUSIONS

To be effective in selecting aircrew helmets to prevent concussive head injuries in survivable helicopter crashes, the current pass-fail criterion of 400 G should be reduced to 150 G. While the SPH-4 aviator helmet adequately protects against penetrating types of head injury, its energy absorbing qualities do not adequately protect against concussive head injuries. The severity of impact surfaces encountered by US Army aircrewmen in survivable helicopter crash situations seldom exceed that of a flat surface. An SI value of 1500 and an HIC value of 1000, currently used as concussive threshold values by NOCSAE and DOT, respectively, exceed the level at which concussion occurs.

## REFERENCES

- American National Standards Institute. 1971. Specifications for protective headgear for vehicular users. New York: American National Standards Institute. ANSI 290.1-1971.
- British Standards Institution. 1960. Protective helmets and peaks for racing car drivers. London: British Standards House. British Standard 2495.
- Chou, C. C. and Nyquist, G. W. 1974. Analytical studies of the head injury criterion (HIC). Presented at SAE Automotive Engineering Conference; 1974 Feb 25-Mar 1; Detroit, MI. New York: Society of Automotive Engineers, Inc. SAE No. 740082.
- Department of Transportation, National Highway Traffic Safety Administration. 1972. Occupant crash protection-head injury criterion S6.2 of MVSS 571.208. Washington, DC: National Highway Traffic Safety Administration. Docket 69-7, Notice 17.
- Gadd, C. W. 1966. Use of weighted impulse criterion for estimating injury hazard. In: *Tenth Stapp Car Crash Conference*; 1966 Nov 8-9; Holloman AFB, NM. New York: Society of Automotive Engineers, Inc. p 164-174.
- Hodgson, V. R. 1975. National Operating Committee on Standards for Athletic Equipment football helmet certification program. *Medicine and Science in Sports*. 7:225-232.
- Joint Committee of The American Medical Association, The Society of Automotive Engineers, The American Association of Automotive Medicine. 1976. The Abbreviated Injury Scale. 1976 revision. Morton Grove, IL: American Association of Automotive Medicine.
- Department of the Army. 1975. *Helmet, flyer's protective, SPH-4*. Natick, MA: US Army Natick Research and Development Command. MIL-H-43925.
- Snively, G. G. and Chichester, C. O. 1961. Impact survival levels of head acceleration in man. Aerospace Medicine. 32:316.
- Swearingen, J. J. 1971. Tolerances of the human brain to concussion. Washington, DC: Federal Aviation Administration. FAA-AM-71-13.

# INITIAL DISTRIBUTION

Center Cameron Station Alexandria, VA 22314	(12)	US Army Research & Technology L Ames Research Center, M/S 215-1 Moffett Field, CA 94035	abs (1)
Under Secretary of Defense for Research and Engineering ATTN: Military Assistant for Medical and Life Sciences Washington, DC 20301	(1)		(1)
Uniformed Services University of the Health Sciences 4301 Jones Bridge Road Bethesda, MD 20014	(1)	Director Army Audiology & Speech Center Walter Reed Army Medical Center Forest Glen Section, Bldg 156 Washington, DC 20012	(1)
Commander US Army Medical Research and Development Command ATTN: SGRD-SI (Mrs. Madigan) Fort Detrick Frederick, MD 21701	(5)	Harry Diamond Laboratories Scientific & Technical Informat Offices 2800 Powder Mill Road Adelphi, MD 20783	ion (1)
Redstone Scientific Information Center ATTN: DRDMI-TBD US Army Missile R&D Command Redstone Arsenal, AL 35809	(1)	US Army Ordnance Center & Schoo Library, Bldg 3071 ATTN: ATSL-DOSL Aberdeen Proving Ground, MD 21005	1 (1)
US Army Yuma Proving Ground Technical Library Yuma, AZ 85364	(1)	US Army Environmental Hygiene Agency Library, Bldg E2100 Aberdeen Proving Ground, MD 21010	(1)
US Army Aviation Engineering Flight Activity ATTN: DAVTE-M (Technical Libral Edwards AFB, CA 93523		Technical Library Chemical Systems Laboratory Aberdeen Proving Ground, MD 21010	(1)
US Army Combat Developments Experimentation Command Technical Library HQ, USACDEC Box 22			•
Fort Ord, CA 93941	(1)		

US Army Materiel Systems Analysis Agency ATTN: Reports Distribution Aberdeen Proving Ground, MD 21005	(1)	Chief Benet Weapons Laboratory LCWSL, USA ARRADCOM ATTN: DRDAR-LCB-TL Watervliet Arsenal Watervliet, NY 12189 (1)
Director Biomedical Laboratory Aberdeen Proving Ground, MD 21010	(1)	US Army Research & Technology Labs Propulsion Laboratory MS 77-5
HQ, First United States Army ATTN: AFKA-MD (Surgeon's Ofc) Fort George G. Meade, MD 20755 Director	(1)	US Army Field Artillery School Library Snow Hall, Room 16 Fort Sill, OK 73503 (1)
Ballistic Research Laboratory ATTN: DRDAR-TSB-S (STINFO) Aberdeen Proving Ground, MD 21005	(2)	US Army Dugway Proving Ground Technical Library Bldg 5330 Dugway, UT 84022 (1)
US Army Research & Development Technical Support Activity Fort Monmouth, NJ 07703	(1)	US Army Materiel Development & Readiness Command ATTN: DRCSG 5001 Eisenhower Avenue Alexandria, VA 22333 (1)
CDR/DIR US Army Combat Surveillance & Target Acquisition Laboratory ATTN: DELSC-D Fort Monmouth, NJ 07703	(1)	US Army Foreign Science & Technology Center ATTN: DRXST-IS1 220 7th St., NE Charlottesville, VA 22901 (1)
US Army Avionics R&D Activity ATTN: DAVAA-O Fort Monmouth, NJ 07703 US Army White Sands Missile	(1)	Commander US Army Training & Doctrine Command ATTN: ATCD Fort Monroe, VA 23651 (2)
Range Technical Library Division White Sands Missile Range New Mexico 88002	(1)	Commander US Army Training & Doctrine Command ATTN: Surgeon Fort Monroe, VA 23651 (1)

US Army Research & Technology Lab Structures Laboratory Library NASA Langley Research Center	os	Commander US Army Health Services Command ATTN: Library	l
Mail Stop 266 Hampton, VA 23665	(1)	Fort Sam Houston, TX 78234	(1)
Commander 10th Medical Laboratory ATTN: DEHE (Audiologist) APO New York 09180	(1)	Superintendent US Army Academy of Health Scien ATTN: Library Fort Sam Houston, TX 78234	ces
Commander US Army Natick R&D Command ATTN: Technical Librarian Natick, MA 01760	(1)	Commander US Army Airmobility Laboratory ATTN: Library Fort Eustis, VA 23604	(1)
Commander US Army Troop Support & Aviation Materiel Readiness Command		Air University Library (AUL/LSE Maxwell AFB, AL 36112	(1)
ATTN: DRSTS-W St. Louis, MO 63102	(1)	US Air Force Flight Test Center Technical Library, Stop 238 Edwards AFB, CA 93523	(1)
Commander US Army Aviation R&D Command ATTN: DRDAV-E P.O. Box 209 St. Louis, MO 63166	(1)	US Air Force Armament Developme & Test Center Technical Library Eglin AFB, FL 32542	ent (1)
Director US Army Human Engineering Laboratory ATTN: Technical Library Aberdeen Proving Ground, MD 21005	(1)	US Air Force Institute of Techn (AFIT/LDE) Bldg 640, Area B Wright-Patterson AFB, OH 45433	
Commander US Army Aviation Research & Development Command ATTN: Library P.O. Box 209	, - ,	US Air Force Aerospace Medical Division School of Aerospace Medicine Aeromedical Library/TSK-4 Brooks AFB, TX 78235	(1)
St. Louis, MO 63166	(1)	Director of Professional Service HQ, USAF/SGES Bolling AFB Washington, DC 20332	ces

Human Engineering Division Air Force Aerospace Medical Rese Laboratory ATTN: Technical Librarian Wright-Patterson AFB, OH 45433	arch	US Navy Naval Air Development Center Technical Information Division Technical Support Department Warminster, PA 18974	(1)
US Navy Naval Weapons Center Technical Library Division Code 2333 China Lake, CA 93555	(1)	Human Factors Engineering Divis Aircraft & Crew Systems Techno Directorate Naval Air Development Center Warminster, PA 18974	
US Navy Naval Aerospace Medical Institut Library Bldg 1953, Code 012 Pensacola, FL 32508	e (1)	US Navy Naval Research Laboratory Libra Shock & Vibration Information ( Code 8404 Washington, DC 20375	
US Navy Naval Submarine Medical Research Lab Medical Library, Naval Submarine Base Box 900		Director of Biological & Medica Sciences Division Office of Naval Research 800 N. Quincy Street Arlington, VA 22217	al (1)
Groton, CT 06340  Director Naval Biosciences Laboratory Naval Supply Center, Bldg 844	(1)	Commanding Officer Naval Medical R&D Command National Naval Medical Center Bethesda, MD 20014	(1)
Oakland, CA 94625  Naval Air Systems Command Technical Library AIR 950D Rm 278 Jefferson Plaza II	(1)	Commanding Officer Naval Biodynamics Laboratory P.O. Box 29407 Michoud Station New Orleans, LA 70129	(1)
Department of the Navy Washington, DC 20351 US Navy	(1)	FAA Civil Aeromedical Institute ATTN: Library	
Naval Research Laboratory Librar Code 1433 Washington, DC 20375	y (1)	Box 25082 Oklahoma City, OK 73125	(1)
Department of Defence R.A.N. Research Laboratory P.O. Box 706 Darlinghurst, N.S.W. 2010 Australia	(1)	DCIEM/SOAM MAJ J. Soutendam (Ret.) 1133 Sheppard Avenue West P.O. Box 2000 Downsview, Ontario M3M 3B9	(1)

Canadian Society of Avn Med c/o Academy of Medicine, Toronto ATTN: Ms. Carmen King 288 Bloor Street West Toronto, Ontario M5S 1V8

COL F. Cadigan DAO-AMLOUS B Box 36, US Embassy FPO New York 09510

MSHA Information Center Library P.O. Box 25367 Denver, CO 80225 Staff Officer, Aerospace Medicine RAF Staff British Embassy 3100 Massachusetts Avenue, N.W. (1) Washington, DC 20008 (1)

Dr. E. Hendler
Code 6003
Naval Air Development Center
(1) Warminster, PA 18974 (1)

(1)